

SCHEDULE OF SPECIFICATIONS AND QUANTITIES FOR FURNISHING WORKS OF ATM AT PROPOSED PURULIA MUNSIFDANGA BRANCH FOR UCO BANK					
SL. NO	DESCRIPTION	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	FALSE CEILING (2 ft x 2 ft grid ceiling) .Providing and fixing grid false ceiling (Armstrong or equivalent) with 12mm thick mineral fibre acoustic tiles with crisp.	60	sft		
2	MAIN ENTRANCE FRAMELESS GLASS DOOR				
	P & E glazed frameless glass door made out of 12mm thick toughened glass work with pencil polish edges all around. Door shall be fixed with double leaf (2.5ft each) at main entrance & the top edge firmly connected with solid partition which further jointed to roof lintel/beam through proper wooden frame work & glass shall be fitted with PATCH FITTING assembly inclusive of top and bottom patches. Floor spring & all necessary hardware such as bottom lock, SS brushed handle of 2'0" long 1"dia on both sides.	21	sft		
3	12mm TOUGHENED FIXED GLASS				
	Providing and erecting fixed type frameless glass partition as per drawing or direction. The glazeing shall be done with 12mm thick machine polished toughened glass. The partition is too be fixed with patch fittings, and / or, continuous polished teak wood glazings beads of approved shape & shade, as directed. All edges of the glass are to be finished with mirror polishing. The work is to include all necessary materials, accessories, labour, tools & tackles.	60	sft		
4	STORAGE				
	Providing & fixing storage to made out of 18mm plywood finished with 1mm laminate as per design. Inside surface to be polished.	7.5	sft		
5	WALL PANELLING WITH ACP				
	Providing & fixing Providing & 3mm thick aluminium composite panel cladding to Shutter/Box paneling of exterior/interior grade with 37.5 x 25 approx 1.1mm thick tubular section aluminium frame work of required Mfr. Of brand Aludecor/Alex/Alubond or Alstrong etc of approved shade as directed both horizontally & vertically @ 600 C/C with 3mm thick PVDF coated on ACP with virgin LPDE core, duly treated with silicon sealant.	160	sft		
6	FIREPROOF PARTITION FOR UPS ROOM				
	Providing and fixing partition with aluminium frame of section 50 mm x 25 mm x 1.5mm with a grid of 600 mm x 600 mm. The frames are to be filled up with Cement boards (EVEREST / CHARMINAR / BISAKA) to be fixed on both sides and screwed to the frame . All exposed surfaces to be finished with putty, primer and two or more coats acrylic emulsion paint.The Aluminium channels are to be fixed on the floor and screws rigidly as per instruction.The grid shall be framed using suitable screws, angle sections . This work to be done for UPS room . Rate to include supply and fixing the door also with all necessary hardware fittings and fixtures as per site dimension.	90	sft		
7	PAINTING OF WALL AND CEILING FOR UPS RM				
	Providing & applying one coat of primer and two coats of acrylic emulsion paint on the new surface with all tools and tackle as per banks approved colour	120	sft		
8	PAINTING OF ROLLING SHUTTER , HOOD AND SIDE CHANNELS:				
	Providing and painting on rolling shutter on both sides with cover hood and side channels , with one coat of primer and two coats of synthetic enamel paint , including scrapping the surface with sirish paper	150	sft		
9	BOXING THE ROLLING SHUTTER HOOD WITH PLY AND LAMINATE				
	Providing and fixing 12mm th. Ply with 1.0 mm th. Laminate to cover up the top hood of the rolling shutter , as per approved colour laminate	48	sft		
10	Supply & fixing of Aluminium Louver in flush door of UPS for ventilation. (Size- 18" x 6")	2	nos		

11	FLOOR SPRING				
	Providing and fixing floor spring of Godrej/Everite/Dorma/Ozone(90kg) two speed in floors for fixing flush doors. Necessary pivot shall be provided at bottom and top so that the flush door shall be operated. The cost includes cutting and making the good of the floor etc complete all as approved and instructed by EIC.	1	set		
12	FROSTED FILM				
	P & F 3M Make Sparkle Series etching film (Frosted) to Main door Glass and other glasses as directed, cut and fixed as per approved slander pattern & design of Bank. (Base price of 3M film Rs.60/- per sqft incl. of Tax, supporting cash memo/ bill to be produced for payment of this item including certificate from 3M dealer certifying use of the product).	45	sft		
13	18" SS Handle for glass door	1	set		
14	UCO BANK Logo	1	nos		
	TOTAL				
	Rupees	+ GST			

