

**B.O.Q OF INTERIOR FURNISHING
WORKS OF
UCO BANK ,BANKURA UNIVERSITY CAMPUS**

OWNER :UCO BANK

BRANCH ADDRESS : BANKURA

**BANKURA UNIVERSITY CAMPUS
KOLKATA- 700020**

CONSULTING ARCHITECT - ARCHI SPACE CONSULTANT

**ADDRESS : 69/3A RAJA S,C MULLICK ROAD "PACIFIC WIND" 2ND FLOOR
NEAR BAGHAJATIN HOSPITAL
KOLKATA - 700047 CONTACT - 9830006396**

DATE : 20.06.2023

ESTIMATE OF INTERIOR FURNISHING WORK- UCO BANK , BANKURA

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
A.	FALSE CEILING				
A.1	False Ceiling - Gypsum Board: (Including Future Expansion Area)	460	Sq.ft.		
	Providing & Fixing suspended gypsum false ceiling, which includes providing and fixing G.I. Perimeter channels of size 0.55mm thick having one flange of 20mm and another flange of 30mm & a web of 27mm along with perimeter of ceiling screws fixed to brick wall / partition with the help of nylon sleeves and screws at 600mm centers then suspending G.I. Intermediate channels of size 45mm X 0.9mm thick with 2 flanges of 15mm each from the soffit at 1220mm centers with ceiling angle of width 25 X 10mm X 0.55mm thick fixed to soffit with G.I. & steel expansion fastners only, "Fastners" shall be used for ceiling supports. Ceiling section of 0.55mm thickness having knurled verb of 51.5mm & two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips & in direction perpendicular to the intermediate channel at 457mm centers. 12.5mm tapered edge gyp board (Conforming to IS-2095-1982) is then screws fixed to ceiling to ceiling section with 25mm dry wait at 230mm centers, additional supports for AC grill shall be fixed as per instructions and AC Plan / Section / Layout. Screw fixing is done mechanically either with screw driver of drilling machine with suitable attachment. The boards are to be jointed and finish so as having a flush look, which includes filling and finishing the tapered and square edges of the boards with jointing compound, paper tape & two coats of primer suitable for Gyp board. Note :- For light fittings, grills diffusers and cutouts, speakers, fire detectors etc. have to be made with the frame of perimeter channels of size 20 X 27 X 30mm X 0.545mm thick, supported suitably as per direction of Architect, Electric or A.C. Consultants & shown as per detail drawing without additional payments. Entire false ceiling shall be finish with 3 coats of ICI. Plastic emulsion paint with necessary scraping, putty, leveling & smooth finish with scaffolding, cleaning etc. Note:- Area of the False Ceiling will be measured in plan i.e. wall to wall. If Any Existing false ceiling should be removed along with debris out of compound without any extra charge.				
A.2	False Ceiling - Armstrong Board: (Including Future Expansion Area)	450	Sq.ft.		
	Providing & fixing in position false ceiling in Armstrong 600 x 600mm x 15 / 16 mm Dune Supreme RH 99 Prima tile with regular edge frame work as specified by Armstrong Co. with suspenders wherever required . Making necessary framework for A.C. ducting , if any , and necessary cutouts for diffusers and light fittings , taping and finishing to proper line & level , including making grooves and trap doors for A.C unit in 18 mm thick M . R . Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. No Drop of design (if any) will be considered as extra measurement it will be considered flat ceiling. The cost includes all the materials, labour, transportation taxes etc., all complete. The work to be completed as per specification and approval of the Architect.				
B.	WOODEN PARTITIONS				
B.1	Full Height Wooden Double Skin Solid Partition With Laminate Finish	190	Sq.ft.		
	Supply & Erecting Solid Partition upto false ceiling, as per drawing & conforming to the following specification: Basic Framework: Well seasoned Malaysian Sall wood sections, treated with two coats of wood preservatives, 50 x 50 mm (minimum) at maximum 2 ft horizontal and vertical spacing as per site condition. Vertical member shall be suitably anchored at floor level to ensure rigidity Skin Membrane: 6 mm BWR grade Ply wood on each face with 2 mm groves as per drawing / instruction. Laminate Finishing: 1.0 mm thk. laminate sheet of combination shades as per instruction (as approved make) on Both face Skirting: The Partition will be finished with 4" wide Skirting finished with 1.0 mm thick Bank's approved colour laminate of approved make on Both Side. Note: Quoted Rates shall include all necessary material, accessories and also allow provisions for electrical / Telephone / Computer wiring conduits and switch boxes etc. (Materials of wiring conduits and switch boxes shall be separately paid for) The work to be completed as per instruction.				
B.2	SEMI HT. Wooden Double Skin Solid Partition With Both Sides Laminate Finish	70	Sq.ft.		

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	Supply & Erecting SEMI HT. (4'-6") Solid Partition as per drawing & conforming to the following specification: Basic Framework: Well seasoned Malaysian Sall wood sections, treated with two coats of wood preservatives, 50 x 50 mm (minimum) at maximum 2 ft horizontal and vertical spacing as per site condition. Vertical member shall be suitably anchored at floor level to ensure rigidity Skin Membrane: 6 mm BWR grade Ply wood on each face with 2 mm groves as per drawing / instruction. Finishing: 1.0 mm thk. laminate sheet of combination shades as per instruction (as approved make) on both face Skirting: The Partition will be finished with 4" wide Skirting finished with 1.0 mm thick Bank's approved colour laminate of approved make on both sides. Note: Quoted Rates shall include all necessary material, accessories and also allow provisions for electrical / Telephone / Computer wiring conduits and switch boxes etc. (Materials of wiring conduits and switch boxes shall be separately paid for) The work to be completed as per instruction.				
B.3	FULL HT. Wooden Partly Glazed Partition With Laminate Finish	400	SFT		
	Supply & Erecting Partly Glazed Partition upto ceiling, as per drawing & conforming to the following specification: Basic Framework: Well seasoned Malaysian Sal wood 2" x 1 1/2" sections treated with two coats of wood preservatives, (minimum) at maximum 2ft horizontal or vertical spacing as per site condition. Vertical member shall be suitably anchored at floor level to ensure rigidity. Skin Membrane: 6 mm BWR grade Ply wood on each face with 2 mm groves as per drawing / instruction. Finishing: 1.0 mm thk. laminate sheet of combination shades as per instruction (as approved make) on both sides. Skirting: The Partition will be finished with 4" wide Skirting Finished with 1 mm thick Laminate of approved make & Colour. Glazing: 8 mm. thk. Clear float glass with pencil polish edges from 3'-0" to 6'-6" fixed with continuous wall nut / wenge. It should be fixed with teak wood beading (size - 30mm x 20mm) all around, finished with melamine polished. Polishing will be the same colour as that lamination i. e. cedar finished. The rate should be including cost of decorative etching on on side of the glass. All complete. Note: Quoted Rates shall include all necessary material, accessories and also allow provisions for electrical / Telephone / Computer wiring conduits and switch boxes etc. (Materials of of wiring conduits and switch boxes shall be separately paid for). The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete. as per instruction.				
B.4	CASH PARTITION	40	SFT		
	Same as - Wooden Double Skin Partly Glazed Partition. Glazing : Strips of 12 mm. thk. clear float glass with pencil polish edges from 3'-6" to 6'-6" fixed with continuos wall nut / wenge. It should be fixed with teak wood beading (size - 30mm x 20mm) all around, finished with natural polished. Polishing will be the same colour as that lamination i. e. cedar finished. A cutout 3" throughout in glass work (similar to front) for official transaction. Above 6'-6" ht. the partition will be finished with 1.0 mm thick Laminate finish on both sides. The rate should be including cost of decorative etching on on side of the glass. All complete. Intermediate trays: There will be provision for small trays / windows for transferring of small copy either from the banking area to the cash cabin or between the cash cabins. it should be finished with 1.0 mm thick Bank's approved colour laminate of approved make. its edges to be same finish. it should have a small door finished with laminate and fitted with all necessary fittings as per instruction. Note : Quoted Rates shall include all necessary material, accessories and also allow provisions for electrical / Telephone / Computer wiring conduits and switch boxes etc. (Materials of of wiring conduits and switch boxes shall be separately paid for). The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete. The work to be completed as per instruction.				
C.	GLASS BARRIER	50	Sq.ft.		
	Providing and Fixing glass barrier in front of work station made out of 8 mm thick polished edged float glass with teak wood beading (size - 30mm x 20mm) all around, finished with melamine polished. Polishing will be the same colour as that lamination i. e. cedar finished. The erection of divider shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories. The rate should be including cost of decorative etching on on side of the glass. all complete. The work to be completed as per instruction of the Architect.				
D.	GLASS DIVIDER	50	Sq.ft.		

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	8mm. thk. clear float glass divider on table top for separation of each workstation with pencil polish edges. It should be fixed between two tables with teak wood beading (size - 30mm x 20mm) all around, finished with melamine polished. Polishing will be the same colour as that lamination i. e. cedar finished. The erection of divider shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories. The rate should be including cost of decorative etching on on side of the glass. all complete. The work to be completed as per instruction of the Architect.				
E.	WRITING LEDGE (4'-0" X 1'-6" X 1'-6")	1	NOS		
	Providing & fixing WRITING LEDGE made out of 19 mm BWR ply frame for sides, which shall be finished Laminate of approved make / colour 1.0 mm thk laminate. 12mm thick CLEAR Glass shall be fixed at top & side level with polish at exposed sides. 8mm thick CLEAR Glass shall be fixed vertically at every 4" c/c with smooth polishing at 4 sides and instructions of the Architect.				
F.	SUGGESTION BOX & CHEQUE DEPOSIT BOX				
	Providing and fixing suggestion box & cheque deposit box 1'-6" x 1'-6" x 6" with 1" wide slit for inserting cheques & letters (individual) made out of 18 mm BWR block board and finished with 1.0 mm thk laminate & inside to be synthetic enamel painted. A 1" high slit & small door with key and locking arrangement to be done for dropping & taking out the slips, all complete as per instruction.				
F.1	Suggestion box	1	No.		
F.2	Cheque deposit box	1	No.		
G.	SOFT BOARD	35	Sq.ft.		
	Soft board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with fabric with necessary moulding duly polished along the periphery.				
H.	Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt	2	Nos.		
I.	DOOR				
	Providing and fixing solid core flush door of 38 mm thk. Finished with 1 mm thk. approved colour laminate . A wooden cover moulding of 3"x3/4" thk. white beech /teak wood with polish shall be provided. 8 mm thk. clear float glass with etching (approved design) shall be provided with 1 1/2"x3/4" thk. White beech/teak wood moulding with polish for partly glazed door. In case of vision panel door 18"x9" made out of 8 mm thk. Clear glass with moulding with polish to be provided. The rate shall be inclusive of 4" s/s hinges, door stopper, screws, 10" 'H' shape s/s handle (Kitch), dead lock, key hole cover, tower bolt, door closer of approved make. All edges of the door to be covered with necessary lipping with polish. The work should be completed as per specification, design and approval of Architect. Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wood / sal wood (seasoned) section with natural polish. The doors fitted with door closers shall be provided 3" x 1 1/2" white beech / Teak wood section with natural polish for door frame work.				
I.1	Partly glazed door -(WPGD-1) - 3'-0" x 6'-6"	2	Nos.		
I.2	Partly glazed door -(WPGD-2) - 3'-0" x 6'-6"	2	Nos.		
I.4	Wooden partition door - (WPD-1)- 3'-0" x 6'-6"	3	Nos.		
I.6	Glass door -(GD-2) - 5'-0" x 6'-6"	1	Nos.		
I.7	Flush door -(D-1) - 3'-11" x 6'-6"	1	Nos		
I.8	Flush door -(D-2) - 2'-6" x 6'-6"	4	Nos		
I.7	Flap door -(FD-1) - 3'-0" x 4'-6"	1	Nos.		
I.8	pvc door - 1'-9" x 6'-6"	2	Nos.		
I.9	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS) GD-1	50	Sqft.		
	Providing and fixing frameless fully glazed 12mm thk toughened float glass door fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, srews, sealent wherever required and SS cover over patch fittings. Rate shall include approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items. The work should be completed as per specification, design and approval of Architect.				
J.	FULLY GLAZED PARTITION ENTRANCE - WITH TOUGHENED GLASS USING OZONE / HAFFLE / YALE / GODREJ MAKE FITTINGS	80	Sqft.		

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed in Brickwall. The work should be completed as per specification, design and approval of Architect.				
K.	TABLE				
	Providing, fixing and fittings in position tables (6" projecting customer side) & 2'-6" ht. made out of 19 mm thk BWR block board for top, sides and front of approved make finished with 1.0 mm laminate as per design in all visible areas. The table will be supported on right side by a 1'-4" wide drawer unit consisting of one drawer and one filing drawer and foot rest on the other side. The front of the drawer unit will be made out of 19 mm thk. BWR block board, other sides made out of 12 mm thk BWR ply and 4" skirting throughout (Foot rest). All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface will be 1 coat primer and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping with melamine polished. Polishing will be of the same color as that of lamination i.e., of Cedar finish. The drawers and shutters to be provided with drawer sliding channels, S/S 4" long handles, s/s hinges, locks etc all necessary accessories. Wire manager for each (approved colour) will be provided, all complete. NOTE : First drawer at each work station must have shelves for segregating currency notes pens/staplers / stamps etc. Drawer at each workstation to divided in 2 equal parts by a horizontal partition and the front partition among these to be divided into 3 equal partitions by vertical partitions.				
K.1	B.M.C. Table with Glass Top (3'-0" DEPTH X 2'-6" HT.)	3	RFT		
K.3	OFFICER/ C.M./ CREDIT DEPTT./ FOREX & NPA/ SECRETARY/ CHIEF CONCERRENT AUDITOR TABLE (2'-6" DEPTH X 2'-6" HT.)	12	RFT		
K.4	Black powder coated key board tray with slide channel	20	NOS		
	Providing and making a table of over all size of top as mentioned above. It shall consist of 19mm thk. BWR Ply top as per design (double edge on outer edge with 37mm x 10mm thk moulding with steam beach wood on the edges) supported on three boxes of size 24" x 6" made of 19mm thk. BWR Ply inter connected with boxing 4" x 6" (as approved by bank / architect). All external surfaces to be finished in 1mm laminate of approved shade (sude finish).The work should be completed as per specification, design and approval of Architect.				
L.	CASH COUNTER				
	Providing and fixing the cash counters along with front partition all complete. Providing & fixing 2'-6" (w) x 2'-6" (h) working table top made of 19 mm thick. BWR block board of approved make. It should have a customer transaction top, 6" projecting on the customer side at a height of 1'-0" from working table. Above the customer transaction top does making a total height 3'-6". Granite top (Black galaxy) 3/4" thick. will be placed on transaction top which is cut and shaped with edges round polished. Both the working table and transaction top will be rested & supported together by a front apron (Double skin Partition) finished with 1.0 mm thick. Laminate as per instruction. Below the Working table will be 1'-4" wide & 2'-0" deep drawer unit consisting of Three drawers and foot rest on the other side. The front of the drawer unit will be made out of 19 mm thk. BWR block board, other sides made out of 12 mm thk BWR ply and 4" skirting throughout (Foot rest). All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface will be 1 coat primer and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping with melamine polished. Polishing will be of the same color as that of lamination i.e., of Cedar finish. The drawers and shutters to be provided with drawer sliding channels, S/S 4" long handles, s/s hinges, locks etc all necessary accessories. Wire manager for each (approved colour) will be provided, all complete.				
	Providing and Fixing glass barrier in front of cash counter (above the the transaction top) made out of 12 mm thick polished edged float glass. It shall have 25mm x 20mm teakwood beading (as approved) to hold the glass from sides and top (optional). Etching to be done wherever required. The rates shall include for cutting (in geometrical shape, center bottom part of the transaction top) and polishing the edges, The rate should be including cost of decorative etching on on side of the glass, all complete to the satisfaction. NOTE: First drawer at each work station must have shelves for segregating currency notes pens/staplers / stamps etc. Drawer at each workstation to divided in 2 equal parts by a horizontal partition and the front partition among these to be divided into 3 equal partitions by vertical partitions.				
L.1	Cash Table	12	RFT		
L.2	Glass Barrier (Front)	40	SFT		

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
L.3	Black powder coated ready made key board tray with slide channel	2	NOS		
N.	LOW HT. STORAGES (1'-6" DEPTH X 2'-6" HT.)	120	SFT		
	Providing and fixing Low height Cabinet made out of made out of 19 mm BWR ply, 6 mm thk. Ply for back finished and 4" skirting throughout. Division of shutters shall be made equally according to the length of the storage. A 19 mm thk. Fixed BWR Ply shelf on battens shall be provided at 16" intervals from the base. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping with melamine polished. Polishing will be of the same color as that of lamination i.e., of Cedar finish. Cost of all fitting like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary hardware shall be inclusive, all complete. As per drawing and instruction.				
O.	FULL HT. STORAGES (1'-6" DEPTH X 7'-0" HT.)	140	Sq.ft.		
	Providing and fixing Full height Cabinet made out of made out of 19 mm BWR ply, 6 mm thk. Ply for back finished and 4" skirting throughout. Division of shutters shall be made equally according to the length of the storage. A 19 mm thk. Fixed BWR Ply shelf on battens shall be provided at 16" intervals from the base. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping with melamine polished. Polishing will be of the same color as that of lamination i.e., of Cedar finish. Cost of all fitting like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary hardware shall be inclusive, all complete. As per drawing and instruction.				
	TOTAL INTERIOR FURNISHING WORKS				
IN WORDS :					

ESTIMATE FOR INTERIOR FURNISHING WORK OF ATM- UCO BANK, BANKURA

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
A.	False Ceiling - Gypsum Board:	40	Sq.ft.		
	Providing & Fixing suspended gypsum false ceiling, which includes providing and fixing G.I. Perimeter channels of size 0.55mm thick having one flange of 20mm and another flange of 30mm & a web of 27mm along with perimeter of ceiling screws fixed to brick wall / partition with the help of nylon sleeves and screws at 600mm centers then suspending G.I. Intermediate channels of size 45mm X 0.9mm thick with 2 flanges of 15mm each from the soffit at 1220mm centers with ceiling angle of width 25 X 10mm X 0.55mm thick fixed to soffit with G.I. & steel expansion fastners only, "Fastners" shall be used for ceiling supports. Ceiling section of 0.55mm thickness having knurled verb of 51.5mm & two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips & in direction perpendicular to the intermediate channel at 457mm centers. 12.5mm tapered edge gyp board (Conforming to IS-2095-1982) is then screws fixed to ceiling to ceiling section with 25mm dry wait at 230mm centers, additional supports for AC grill shall be fixed as per instructions and AC Plan / Section / Layout. Screw fixing is done mechanically either with screw driver of drilling machine with suitable attachment. The boards are to be jointed and finish so as having a flush look, which includes filling and finishing the tapered and square edges of the boards with jointing compound, paper tape & two coats of primer suitable for Gyp board. Note :- For light fittings, grills diffusers and cutouts, speakers, fire detectors etc. have to be made with the frame of perimeter channels of size 20 X 27 X 30mm X 0.545mm thick, supported suitably as per direction of Architect, Electric or A.C. Consultants & shown as per detail drawing without additional payments. Entire false ceiling shall be finish with 3 coats of ICI. Plastic emulsion paint with necessary scraping, putty, leveling & smooth finish with scaffolding, cleaning etc. Note:-Area of the False Ceiling will be measured in plan i.e. wall to wall. If Any Existing false ceiling should be removed along with debris out of compound without any extra charge.				
	Supply & Erecting Solid Partition FULL HT. as per drawing & conforming to the following specification: Basic Framework: Well seasoned Malaysian Sall wood sections, treated with two coats of wood preservatives, 50 x 50 mm (minimum) at maximum 2 ft horizontal and vertical spacing as per site condition. Vertical member shall be suitably anchored at floor level to ensure rigidity Skin Membrane: 6 mm BWR grade Ply wood on each face with 2 mm groves as per drawing / instruction. Finishing: 1.0 mm thk. laminate sheet of combination shades as per instruction (as approved make) on both face Skirting: The Partition will be finished with 4" wide Skirting finished with 1.0 mm thick Bank's approved colour laminate of approved make on both sides. Note: Quoted Rates shall include all necessary material, accessories and also allow provisions for electrical / Telephone / Computer wiring conduits and switch boxes etc. (Materials of wiring conduits and switch boxes shall be separately paid for) The work to be completed as per instruction.				
	Providing and fixing Full height Cabinet made out of made out of 19 mm BWR ply, 6 mm thk. Ply for back finished and 4" skirting throughout. There will be vertical dividers of same block boards at maximum 4 ft apart on which the shutters will be fitted with stainless steel hinge. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping with melamine polished. Polishing will be of the same color as that of lamination i.e., of Cedar finish. Cost of all fitting like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary hardware shall be inclusive, all complete. As per drawing and instruction.				
D.	DOOR				
	Providing and fixing solid core flush door of 38 mm thk. Finished with 1 mm thk. approved colour laminate . A wooden				
D.1	Flush door -(D2) - 2'-6" x 6'-6"	1	Nos.		
D.2	MAIN ENTRANCE DOOR CUM FIXED GLAZING with sticker design bank's name,logo,eatching,band etc				
	a) Openable Portion	21	Sq.ft.		
	b) Fixed Portion	35	Sq.ft.		
	Providing & fixing fully glazed pivoted door at the main entrance consists of 6"x2" c.p.t. wood frame for top rail and 4"x2" c.p.t. wood frame for bottom rail finished with 1.0 mm thk laminate, sides with 1" X 1" c.p.t.wood mouldings of approved design. 12mm thk. toughened glass & finish handle (1'-0" long- both inside & outside) to be fixed on both sides & proper locking arrangement in bottom rail to be done. The rate should include lipping, moulding, beading, sticker design bank's name, logo, Pull & Push Plate, & heavy duty floor spring of approved make. The work to be completed as per drawing and instruction.				
F.	ACP PANELING	40	Sq.ft.		

	Supplying , fabricating and installing Aluminium Composite Panel (as per approved colours) Cladding to walls and door , comprising of 4mm thick (0.5 mm + 3 mm + 0.5 mm) approved brand acp material with back Al frame work in 0 level with joints and sizes as per front elevation working drawing. All complete with approved aluminium sub structure, aluminium brackets ,silicon sealants(all the joints shall in 5 mm grooves filled up with black silicon sealant), gaskets , PVDF coating etc. all compete including bird / vermin proof closer at the bottom and flashing.				
G.	Display Boards for Bank's Advertisement	1	Nos.		
	Providing & fixing in position fameless double Acrylic transparent sheets 2'-6" x 1'-6" mounted with studs on the wall (poster to be sandwiched in between) for display of Bank's advertisement inserted on it. Outer sheet is 5 mm thick and beveled crystal edge polished for ¾" at 8-10 degrees on all sides in the front. Rear sheet is 5 mm thick flat. Rate inclusive of S1 grade aluminium.				
H.	TRAP DOOR & BOXING FOR ROLLING SHUTTERS	50	Sq.ft.		
	Providing and fixing trap doors consisting of 1/4" thk. Marine ply shutters with a clear opening of 4.5" opening for smooth operation of shutters and rest is closed with mirror screws (for opening for servicing). The shutters shall be finished with approved 2.0 mm Aluminium composite sheet, frame of 2" x 1 ½" teak wood sections shall be provided for proper supprot and strength. Rate shall be inclusive of necessary fittings like hinges, ball catches, tower bolts, etc. Complete as per the instructions of Architect.				
I.	FROST FILM / ETCHING FILM OVER GLASS	50	SFT		
	Providing and fixing etching film as directed by Bank/ Architect of glass, to proper level, with out air bubbles / cuts / folds etc. complete.				
	TOTAL INTERIOR FURNISHING WORKS OF ATM				
IN WORDS :					

ESTIMATE FOR UCO BANK ,BANKURA BRANCH		
ARCHI SPACE CONSULTANT		
<u>SUMMARY</u>		
SL. NO.	DESCRIPTION	AMOUNT (Rs.)
1	INTERIOR FURNISHING WORK	
2	INTERIOR -ATM	
	GRAND TOTAL (1 to 2)	
IN WORDS:		

Note:

Cost including all material, labour and Transport charges etc. all complete. The work to be completed as per design, specification and approval of the Bank/Architect.

UCO BANK- BANKURA

LIST OF APPROVED MATERIALS FOR INTERIOR FURNISHING WORK

Sl.No.	Items	Approved make
1	False Ceiling	Armstrong / India Gypsum
2	Wood Frame Work / Wood Section	Malaysian Sal
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach/ White Ceder
4	Door frame	Teak wood / Sal Wood
5	BWR Ply / Block board with ISI mark	Sylvan / Satabdi / Avenger / Archidply / Alishan
6	Flush Door	Sylvan / Satabdi / Avenger / Archidply / Alishan
7	Laminate (1.0 mm thk.)	Sunmica / Euromica / Merino / Airolam
8	Door Closure (Heavy Duty)	Godrej / Archi / Sterling (DC 2000)
9	Floor Spring (Heavy Duty)	Godrej / Archi / Sterling (FS 3000)
10	Door Lock (Dead)	Godrej / Hafele /Hettich / Kich /Doorset / 4C Acme (ML – REG – SS)
11	Door Handles ('H' Shape)	Godrej / Hafele /Hettich / Kich /Doorset / 4C Acme (PHG – HSS)
12	Drawer / Storage Handle (4" / 6")	Kich /Neki / Hassley/EGL (HMS –B – 9122 / 9123)
13	Drawer / Storage Lock (Multipurpose)	Ebco / Hafele /Hettich / Doorset / Godrej / Kombo (502)
14	Screws	GKW / Nettle fold
15	Hinges	CIEF
16	Sliding Telescopic Drawer Channel	Ebco / Kombo
17	Key Board Tray (Metal)	Ebco / Innofitt Systems (KD 510. M)
18	Cable Organiser	Ebco / Innofitt Systems (CM 63.C)
19	Adhesive	Fevicol SH / Fevimate TL
20	Aluminium Door Frame	Jindal
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annums / Window Fashion
23	Glass	Modi /Ashai / Saint Gobain
24	A.C.P	Alu Decor / Alu Bond / Alstone/ Wonder Alu board Accura
25	Ceramic Tiles	Orientbell/Kajaria/ Somany/ Jhonson
26	Vitrified Tiles	Orientbell/Kajaria/ Somany/ Jhonson
27	Paints	(Synthetic Enamel / Acrylic Emulsion) Asain Paints (Colour World) / Berger (Colour Bank)
28	SANITARY FIXTURES & FITTINGS	JOHNSON/ CERA/ JAGUAR
29	All other items not covered above	As per sample approved by Bank/ Architect

