

ONLY EMPANELLED CONTRACTORS OF UCO BANK AT JALANDHAR ZO CAN APPLY

ISSUED TO M/S -- _____

**TENDER DOCUMENT
FOR
FURNISHING OF UCO BANK
AT
KATRA, J & K**

**OFFICE OF THE
DEPUTY GENERAL MANAGER
UCO BANK, JALANDHAR**

**ARCHITECTS:
MITTAL & ASSOCIATES
111 B.S.F. COLONY, NEAR H.M.V. COLLEGE
JALANDHAR CITY- 144001
PHONE : 98140 – 89421**

Date of submission of tender: 17.05.2022 upto 01.00 P.M.

Date of Opening of tender: 17.05.2022 at 4.00 P.M.

(Tender to be submitted in the office of DGM, UCO Bank, Zonal Office, Jalandhar)


TENDER NOTICE

Undersigned invites sealed limited tender for Furnishing work of our branch:

1. Katra, J&K.

Tender documents will be issued from our Zonal Office, i.e. SCO 113-114-115, Master Tara Singh Nagar Market, Near BSNL Exchange, Jalandhar or can be downloaded from UCO Bank website : www.ucobank.co.in, and to be submitted along with a fee of INR 500/- (Rupees Five Hundred Only) in the form of Demand Draft favoring UCO Bank.

Opening date of Tenders is 07-05-2022 and last date of receiving Tenders will be 17-05-2022 till 1.00 P.M. Tenders will be opened on same day at 4.00 P.M. at our Zonal Office, i.e. SCO 113-114-115, Master Tara Singh Nagar Market, Near BSNL Exchange, Jalandhar.


Deputy General Manager

To

M/s _____

DETAILS OF TENDER

TENDER FOR THE FURNISHING OF UCO BANK AT KATRA, J&K

| | | |
|----|---------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------|
| 1. | Details of work to be done | Interior/ Furnishing & Allied Electrical works for UCO Bank, at Katra |
| 2. | Form of Contract | Item wise rate |
| 3. | Earnest Money | Rs. 15,000/- (Fifteen thousand only) in form of Demand Draft favoring UCO Bank Zonal Office payable at Jalandhar. |
| 4. | Period of Contract / time of Completion | 4 Weeks |
| 5. | Liquidated damages for non - completion of work in time | 1.0 % of the contract value per week subject to a max of 10% of the contract value |
| 6. | Defect Liability Period | 12 months (Twelve months) from the date of virtual completion as certified by Architect / employer. |
| 7. | Retention amount for 12 months | 3 % of the total bill |
| 8. | Period of submitting of Final Bill. | 15 days from the date of completion |
| 9. | Mobilization Advance / Secured Advance | No Mobilization Advance/ secured Advance will be given to the Contractor. |


Deputy General Manager

UCO Bank Jalandhar

TENDR FOR THE FURNISHING OF UCO BANK AT KATRA, J & K

Tenders duly sealed & properly super scribed are invited under single bid system as per the format given at Appendix – I (Financial Bid) for Furniture & Fixing Work, & Electrical Works. General terms and conditions are as under:

TERMS & CONDITIONS

1. Opening date of tender 07.05.2022.
2. Closing date of tender 17.05.2022, 1300 hrs. Tender received after due date and time will not be entertained.
3. Envelop should be super scribed as "TENDER FOR FURNISHING WORK OF BRANCH OFFICE KATRA, J&K" and addressed to "Zonal Office, UCO Bank, General Administration Department, SCO-113,114,115, Master Tara Singh Nagar Market, Near BSNL Exchange, Jalandhar (Punjab)".
4. In case of unscheduled holiday on the closing/opening day of bid, the next working day will be treated as scheduled prescribed day of closing/opening of the Tender.
5. The Tender document fee of Rs. 500/- (Rupees Five Hundred Only) (Non-Refundable); the Earnest Money Deposit (AMD) of Rs. 15,000/- (Rupees Fifteen Thousand Only) are to be enclosed in the form of Demand Drafts/pay orders drawn separately favoring "UCO Bank, Zonal Office, Jalandhar" payable at Jalandhar, with the Tender documents, failing which the tender will be rejected.
6. In case of any clarification, queries, tenderor may contact, Zonal Office, UCO Bank General Administration Department , Jalandhar on working days between 11.00 A.M. to 04.00 P.M.
7. Any effort by tenderor to influence Bank's processing of tender or award of contract may result in rejection of the tenderor tender.
8. Tenderor may present them at the time of opening of tenders if they wish to do so.

GENERAL CONDITIONS

1. The Contractor shall sign each page of this tender.
2. Payment to the Contractor Agency shall be made as per actual work done at site.
3. Quantity of work may increase or decrease at site as per requirement, which shall not affect the rates quoted by the contractor.
4. Furnishing works including electrical works etc. shall be done to the complete satisfaction of bank and Architect-in-charge.
5. All teak / Cedar wood/ rubber wood to be used should be knotless which is to be polished with all background surface preparation coarses maintaining the visibility of wood grains.

6. The rates to be quoted shall include the cost of material, labour charges, carriage, sales tax, or any / all other taxes any required hardware etc.
7. The contractor agency shall keep particular vigil on his workers / carpenters/ painters etc. to maintain very good workmanship of all items, failing which no payment shall be made and no claim of material/ labour used shall be made to him in any case, and the same work shall be executed by him again without charging any extra cost.
8. All rates shall be quoted in words & figures & any cutting over writing shall be signed.
9. All items to be executed as per drawings, if any change is required, the same shall be brought to the notice of Architect-in-Charge.
10. Any tender / quotation containing clerical or arithmetical mistakes shall be rejected.
11. Any addition, alteration or correction shall be signed and stamped properly.
12. Contractor agencies are advised (before quoting the rates) to inspect the sites of the proposed work. He must go through all drawings and specifications and documents.
13. The Bank reserves the right to accept / reject any tender/ quotation without assigning any reason.
14. The contractor agency should have already executed works of furnishing interiors & exteriors, civil works of very good workmanship.
15. Quality of material and workmanship rejected by the Architect / Concerned authorities shall be removed immediately by the contractor and rectified / replaced.
16. No advance payment shall be made to the Contractor on supply of any material supplied at site for execution. Payment shall only be made on execution of any concerned / particular item.
17. The rates shall include the cost of coat of anti termite treatment on all wooden frame work and all commercial ply / board used for partitions and paneling, furniture etc. The contractor/ s shall have to dismantle & dispose the existing false ceiling, counters, tables & partitions within the quoted cost of the total furnishing works.
18. Rates for partitions, paneling, wall cladding and false ceiling shall include cutting and making good of necessary cut-outs/ chiseling to be made for electrical conduits, switch boards etc.
19. Bank shall not be responsible for any loss or damage to the contractor/ labour due to any natural calamity during the course of construction. Contractor is liable to make good all the damages if any, till the work is completed and handed over to the Bank authorities.
20. Any payment to the contractor on account of execution of work, whether it is running payment or final, shall be verified by the Architect-in-Charge.

21. Unless, otherwise mentioned all materials to be used shall be I.S.I. marked. Failure to do so, the work may be rejected and in that case contractor shall have to remove the defective materials and replace / re-do the work for which no claim shall be entertained.
22. The total work shall be supervised by the Architect-in-Charge and Bank authorities and he/she shall be kept fully informed by the contractor regarding the progress of work.
23. Bank may award the work in part or whole to a single party or any other party.
24. It may please be noted that the Bank is not bound to allot the work to the lowest party. And as such, the allotment of work shall be based on workability of rates quoted by the contractor on account of quality work.
25. The bank reserves the right to reject any or all the tenders without assigning any reason whatsoever.
26. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful tenderor.
27. Earnest money paid by the contractor shall be forfeited by the Bank if contractor fails to undertake the job if he is communicated about acceptance of his rates/tender.
28. The contractor shall take all the necessary precautions while working and to safe guard adjacent property, Bank's property, Bank's Employees, and traffic persons.
29. All the rates quoted are inclusive of removal of existing counters, partitions, wiring, rubbish/debris collected during the progress of work, rejected materials etc.
30. The contractor shall not directly or indirectly sublet the work to other party without written permission of Bank.
31. The quantities mentioned in schedule are provisional and likely to increase/decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit/ business shall be entertained on this account.
32. The Bank reserves the right to distribute the work for which quotations have been called, among more than one parties, if found necessary. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the Bank.
33. All the workers of the contractor must be properly covered by an insurance policy under "Workmen's Compensation Act" and "Fatal Accidents Act". The contractor at his own expenses arrange to effect and maintain until the virtual completion of the contract, insurance policy in the joint name of the Bank and the contractor against this risk to be retained by the Bank until the virtual completion of the work, and

indemnify the Bank from all the liabilities arising out of such events. In case of delay, contractor shall arrange to extend insurance policy till work is completed.

34. All the work should be completed within the specified period in the tender, if the work is delayed due to the reasons beyond the control of the contractor, he should keep intimating the Bank explaining, therein the reasons for such delays, immediately and if in the opinion Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.
35. The contractor shall furnish well in time before work commence at his own cost, colour samples, samples of materials or workmanship that may be called by Bank's Architect / Engineer for approval, Rates quoted shall cover for such preliminary work.
36. All the glass panes, door handles/ hinges, electric fittings, fans, furniture, records, floors etc. are to be thoroughly cleaned after the work is completed.
37. The rates quoted by the contractor shall be firm throughout the duration of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in cost of material and labor.
38. Conditional tenders are liable to be rejected.
39. The successful tenderor is bound to carry out any item of work necessary for the completion of the job even those such items are not included in schedule of quantities.
40. If in any case of work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period, if deemed fit.
41. Decision of the Bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on the terms and conditions of this contract. However, if the matter cannot be resolved then the same shall be referred to the respected qualified person in agreed to both the parties and his opinion shall be binding on both the parties. However, this is precourse to any legal action in this regard.
42. If at any stage during the progress of work, it is observed that the contractor is not progressing the work with due diligence, care of lagging much behind the schedule or fails to gear up the work despite instructions from Bank's Architect, the Employer (Bank) reserves the right to terminate the contract with 7 days notice. In such case the contractor shall be liable to pay the Employer any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposited held by the Bank will be forfeited.

43. Contractor shall follow all rules / regulations in force and should possess the license for employing labour and also follow all safety measures, labour bye laws and shall be responsible for any lapse.
44. At any stage i.e. during the execution of work, any kind of change reqd. whether it is in design or specification, the same has to be incorporated by the contractor.
45. During the course of renovation, the material to be used is to be got verified from the Branch Manager, otherwise no payment will be made.
46. All the contractors are to submit G.S.T. Number, sale tax and income tax PAN No., as required for keeping record for the tender work.
47. All taxes are to be included in tender rate quoted by the contractor and no other tax will be paid by the Bank, excluding G.S.T.
48. Rates of any additional work undertaken will be the rates decided by the Architect and those rates will not be more than the prevailing market rate.

CONTRACTOR

UCO BANK

TENDER FOR THE FURNISHING OF UCO BANK AT KATRA, J & K

FOR FURNISHING WORK TO BE USED

| <u>DESCRIPTION</u> | <u>BRAND</u> |
|---------------------------------------------------|---------------------------------------------|
| a) Board/Ply | : Century, Green Ply, Austin |
| b) Laminate | : Sunmica, Formica, Century |
| c) Door Closer/ Floor spring | : Everite, Doorking, Nitco. |
| d) Drawer & Keyboard, Slide Rails | : Earl Bihari, Ebco (Telescopic) |
| e) Glue for fixing commercial Board / Laminate | : Fevicol (Pidilite) |
| f) Glass | : Triveni, Modi Float, Saint Gobain, Asahi. |
| g) Mortice Latch & Lock | : Godrej, Harrison. |
| h) Multi-Purpose Locks | : Harrison. |
| i) Vertical Blinds | : Vista levelor / Mac. |
| j) Aluminum Sections | : Jindal/Mahavir/Hindalco |
| k) False Ceiling | : Gypsum marked "Gypsteel" / Armstrong |
| l) Synthetic Enamel | : Asian, Nerolac, ICI, Berger |
| m) Emulsion Paint / Plastic Paint | : Asian, Nerolac, ICI, Berger |

SPECIFICATION / BRANDS/MAKE OF ITEMS FOR ELECTRICAL WORK TO BE USED

| | |
|-------------------------------------------|-----------------------------------------|
| -SFU/MCCB/Change over switch/DB | : L&T/Legrand/MDS/Havells. |
| -Voltmeter/Ampere meter | : AE/L&T. |
| -Armored Cable | : Gloster/CCI/Polycab. |
| -PVC Insulated Wires | : Finolex /R.R./Polycab /Havells. |
| -Telephone Cable | : Finolex/Evershine KDK/Delton/Havells. |
| -Data cables & I.O's | : Lucent/ D-link. |
| -Modular switch/ socket/ call Bell/MCB's | : North west/Havells/Anchor Roma. |
| -Light fittings & Lamps | : Philips/Crompton/Wipro. |
| -Ceiling fan/Wall bracket fan/Exhaust fan | : USHA/Crompton/Orient. |

Estimate for Furniture & Fixing Work

UCO BANK, KATRA BRANCH

| S.No. | Description of items | Qty | Unit | Rate (In Rs.) | Amount (In Rs.) |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|------------------|--------------------|
| 1 | SINGLE WINDOW CUBICAL UNIT: | 1 | Each | | |
| | <p>Two S.W.O. Table & One Officer table complete one unit as per standard design with key board and accessories locking devices of Godrej complete in all respect with approved colour & 5'0" ht with glass of 15" on front and 18" on side, 8mm thick first quality Asahi or Modi. with one door as per design.</p> <p>1. Steamed Anegre (equivalent to 366 of M/S Century) - This color will be provided on table top and facade of counters and partitions in strips.</p> <p>2. Sugar maple (Equivalent to F1 1758 of M/s Formica) - This color will be provided at vertical faces of all counter /partition along with facade of the counters/ tables.</p> <p>3. Goncalo Alvez (Equivalent to 1769 of M/s Sunmica) - This color will be provided at skirting. Inside shall be painted with synthetic enamel paint complete in all respects as required by Architect. The 19mm. th. Block board should be (is 1659) of Century / Green /Austin or equivalent. The rate also includes drawer, cabinet box etc. Counters are to be provided with computer keyboard tray of Ebco make code no KBT 45 and drawer and boxes. Also making position for electrical points conduits & switch boxes with plastic round shape 2" diameter openings etc. Also fitting of U.P.S. shelf, foot rest in C.P. Teak wood at the bottom .i.e. complete job in all respects with fittings and accessories like Godrej locks, handle, hinges etc. All Cubical Units to be closed with three no. of doors and one main door. etc. Table Top of Post Foam.</p> | | | | |

| | | | | | |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|--|--|
| | | | | | |
| 2 | OFFICER TABLE: | 1 | Each | | |
| | P/F partly Banking exclusives officers table as per design of size 5'-0"x2'-6"x2'-6" Ht. with keyboard, drawers unit, provision for enplacement of CPU etc. The unit shall be made of 19" thk. Commercial board of Green, duro, century make, with TW gola of size 1.5"x3/4", duly polished on all exposed edges & top of drawers & bottom of the unit, working surfaces shall be provided with 1mm thk. laminate of Formica, Green Lam, Century, Duro of approved shade colour complete hardware, Godrej locks, Hettich sliding rails for drawers & key board shall etc. inside shall be painted with matt synthetic enamel paint of ICI, Asian Burger complete in all respects as per drawings. Side rack 3'-0"x1'6"x2'-6" specifications as above. (as per drawing)Table Top of Post Foam. | | | | |
| 3 | MANAGER TABLE: | 1 | Each | | |
| | Manager Taper Table Size 5'-6"x2'-9"x2'-6" incl. side rack 3'-0"x1'6"x2'-6" specifications as above. (as per drawing)Table Top of Post Foam. | | | | |
| 4 | FALSE CEILING (2'0"x2'0") | 660 | Sft. | | |
| | Ceiling of make Aram strong of 2'x2' grid,with T Section, Powder Coated.10.5mm thk M.S. suspended ceiling horizontally & vertically regular (Single Layer) (G.MFSC-4.1) to be provided as per manufacturers specifications i.e. ceiling lights etc. Complete job. | | | | |
| 5 | VITRIFIED TILES FLOORING:- | 0 | Sft. | | |
| | P/L polished 12mm vitrified tiles flooring of 2'-0" X2'-0".double charge with cement based high polymer modified quick-set tile adhesive in an average 3mm thickness. Including grouting the joint with white cement and matching pigments to be laid over 3" brick rammed ballets over 1.5" thick p.c.c. of double charged either of kajaria or orient or ivy cloure. | | | | |
| 6 | LOW HEIGHT (4'-6") PARTITION WALLS: | 80 | Sqft. | | |

| | | | | | |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|--|--|
| | P/F wooden partition of manager cabin strictly as per drawing made of internal frame of 2" x 2" seasoned partal wood placed at 2'-0" C/C vertically & horizontally frame 6mm thk. Commercially ply of Green, Duro, Century make on both sides. The partition shall 6mm thk. commercial ply with 1mm thk. laminate of for mica, Green Lam, Century make on both sides with horizontal grooves 1/8" x 1/8". These partitions shall have 10mm thk. glass 12" height incl. satin etching & pencil grinding of exposed edges fixed with SSD patch fitting of Approved Make with beading of TW 1/2" X 1 1/2" as per specification of partitions with hardware, the low height partitions shall have rubber wood gola of size 3' x 3/4" which shall be melamine polished as per shade reqd. all complete as per shade approved by Architect in all respects. | | | | |
| 7 | WOODEN PANELLING (UPTO 4'-6" HT.): - | 445 | Sqft. | | |
| | Wooden Panelling on pillars /walls made out of 1mm thk. Laminate of approved colour with grooves as per design over 6mm thk. commercial ply, over GI Studs 1"x2" frame duly, fixed on existing pillar/wall upto reqd. ht. as per drawing & Teak wood lipping out of 1 1/2"x 1 1/2" on top & 3/4"x18"edghing at bottom duly spirit polished incl. framing to be done over hard wood filler battens to make at straight of size 2"x reqd. depth duly anti termite complete job. & in Column Full Ht. up to ceiling level .To the satisfaction of the Architect. | | | | |
| 8 | FULL HT. PARTITION | 90 | Sqft. | | |
| | P/F wooden partition of manager cabin strictly as per drawinged made of internal frame of 2" x 2" seasoned partal wood placed at 2'-0" C/C vertically & horizontally frame 6mm thk. commercially ply of Green, Duro, Century make on both sides. The partition shall 6mm thk. commercial ply with 1mm thk. laminate of for mica, Green Lam, Century make on both sides with horizontal grooves 1/8" x 1/8". these partitions shall have 10mm thk. glass 12" height incl. satin etching & pencil grinding of exposed edges fixed with SSD patch fitting of Approved Make with beading of TW 1/2" X 1 1/2" as per specifcatio of partitions with hardware, the low hight partitions shall have rubber wood gola of size 3' x 3/4" which shall be melamine polished as per shade reqd. all | | | | |

| | | | | | |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-------|--|--|
| | complete as per shade approved by Architect in all respects. | | | | |
| 9 | WOODEN CABINET:- | 30 | Sqft. | | |
| | Providing and fixing storage cabinets incl. openables shutters along wall 1'-6" deep 2'-6" ht. made of 19mm thk. Commercial board & 6mm thk. ply at rear with 1mm thk. Laminate on front, exposed side & top, inside Matt Enamel painting, complete covered with TW goals 20x5mm on all exposed edges duly polished incl. all SS hardware Godrej locks etc. as per requirements/design/drawing. | | | | |
| 10 | ENTRANCE GLASS DOOR | 98 | Sqft. | | |
| | Providing and fixing <u>double shutter</u> glazed door/fixed glazing with float glass 12mm thick with required holes, grinding & polish of edges & cutouts for receiving patch fittings, incl. locks, 15" long handle etc. incl. matching accessories incl. pivot machine make Dorma or Equalent, & connectors etc. The glass shall have Bank's logo of about 2' dia on doors with painted on it. | | | | |
| 11 | NOTICE BOARD:- | 1 | Each | | |
| | Notice Board 3'-0"x2'-0"x6'-0" deep/Suggestion box/Cheque clearing box made of wooden boarder or one side Teak faced block board & 12mm pin up soft board of sita tex make size & glass panel as per design approved by Architect complete in all respects. | | | | |
| 12 | SUGGESTION BOX:- | 1 | Each | | |
| | Suggestion Box Cheque clearing box made of wooden boarder or one side Teak faced block board as per design approved by Architect complete in all respects. | | | | |
| 13 | CUSTOMER VOUCHER STAND:- | 1 | Each | | |
| | Customer voucher stand of size 3'-0"x1'-6"x3'-9" ht. having 6 nos. pigeon holes 9" deep 6"x6" fabricated out of 19mm thk. Board IS:1659 of approved make laminate with 1.5mm thk. FORMICA on horizontal surfaces & 1mm thk. on vertically surfaces & teak wood edging 19mmx1/4" duly spirit polished per the satisfication of Architect/Bank Engineer. Inside surface shall be spirit polished/enamel painted complete job. | | | | |

| | | | | | |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-------|--|--|
| 14 | Plastic Emulsion Paint | 0 | Sqft. | | |
| | Providing & painting with ready mixed Plastic Emulsion Paint of approved brand & manufacturer in all shade on old/new work, two or more coats to give an even shade including scraping, base filling, primer etc. where ever require. | | | | |
| | TOTAL | | | | |

1. No extra work is allowed without written permission from the Bank.
2. Consult Architect if there is any doubt.
3. Use anti -termite board & ply of kitply/ duro / green ply industries or equivalent.
4. Use 1 mm thick laminate as per design.
5. All the taxes are included in the rates. No separate tax/octroi will be paid.
6. All wood work has to be treated with anti termite treatment
7. Glass of make either Modi guard or Asahi.
8. Ply board to be used only of make Greenplay, Centurary, Duro only.
9.
 - a. Steamed Anegre (equivalent to 3666 of M/s Century): This color will be provided on table top and façades of counters & partition strips.
 - b. Sugar Maple (equivalent to FI 1758 of M/s Formica) : This color will be provided at all Counters / partitions along with façade of the counters/tables as per design.
 - c. Goncalo Alvez (equivalent to 1769 of M/s Sunmica) : The color will be provide at skirting as per design.

Estimate for Electrical Work**UCO BANK, KATRA BRANCH**

| Sr. No: | Description of Items | Quantity | Unit | Rate | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|------|--------|
| 1 | Providing wiring with 2x1 Sq.MM. copper conductor PVC insulated wire along with 1 No:-1 Sq .MM copper earth wire in appropriate Size of rigid PVC conduit medium duty with accessories on surface or concealed in wall, beams Slab etc. (modular switch and socket. Multi standard wire shall be used RR Cable polycab, Havel). | 39 | Each | | |
| 2 | Wiring As above for call bell etc. | 1 | Each | | |
| 3 | Providing wiring for independent power plug points with 2x4 Sq. MM. copper conductor and 1.5 Sq. MM. earth wire etc. | 5 | Each | | |
| 4 | Providing wiring for 25 Amp A.C. Starter with 2x4 Sq. MM copper conductor and 1.5 Sq. MM. earth wire in PVC conduit etc. | 4 | Each | | |
| 5 | SITC of Cubical type Control panel 16 SWG CRCA sheet duly painted and used material by detail. | 1 | Each | | |
| i) | 200 Amp 4 pole MCCB PSEB incoming supply | 1 | | | |
| ii) | 160 Amp pole change over switch | 1 | | | |
| iii) | Providing of 4way TPNB DB with MCB (power DB & light DB) | 2 | | | |
| iv) | Bus Bar 200A | 1 | | | |
| V) | Indicators | 1 | | | |
| vi) | VAF meter and CT 100/5 | 1 | | | |
| 6 | Providing of 3 Nos. kit kat 100 Amp With MS Box | 1 | Each | | |
| 7 | P/F of UPS input and output DP 40 Amp with box | 2 | Each | | |
| 8 | S/F of 2x6sq.MM wire and 2.5mm Earth wire panel to UPS room with PVC Conduit 25 mm | 15 | Meter | | |

| | | | | | |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|--|--|
| 9 | Supply and installation of distribution Board double Mattel door Lock able. 12 ways 1 No. 32A DP MCB and 10 No. 6A SPMCB etc. | 1 | Each | | |
| 10 | Supply and drawing 2 pair 0.5mm size Telephone wire thought new PVC conduit from tag block to the location as directed. | 10 | Each | | |
| 11 | Wiring for computer point 4 Nos. Socket and one NO. switch with 1.5 sq.MM wire 1 No. 1 mm earth wire in PVC conduit 25 mm MS box ,Bakelite sheet 3mm thickness. | 5 | Each | | |
| 12(a) | Providing and laying earthing station 60cmx 6cmx6mm copper earth plate as per relevant ISI. The work includes bringing 1 No. copper earth strip 25mmx3mm size in suitable size of G.I. pipe upto ground level with all relevant hardware and accessories such as brass washers brass nuts and bolts and providing masonry enclosure. 300x300x300mm with CI cover plate having locking arrangement water pipe, Funnel etc. The earth plate shall be minimum 3 mtr. Deep and 1.5 mtr. away from the building foundation. | 2 | Each | | |
| (b) | P/F of 1No. 8 SWG copper earth wire ground to main panel | 80 | Mtr | | |
| 13 | SITC of 2x2 light fitting 36 watt LED make Crompton, Havell, Phillips. | 10 | Each | | |
| 14 | SITC of down light ,12 watt LED (Philips, Crompton, Havells) | 11 | Each | | |
| 15 | S/F of 1x28 watt tube light fitting T-5 in complete (Phillips, Crompton, Havells) | 10 | Each | | |
| 16 | S/F of wall bracket fans 400mm sweep (make khaitan, Orient, Crompton) | 3 | Each | | |
| 17 | P/F of fresh air fan 12" sweep 1400 RM Light duty (make Khaitan, orient, Crompton) | 2 | Each | | |
| 18 | S/F of ceiling fan 48" double ball bearing etc.(khaitan, usha, Crompton) | 4 | Each | | |

| | | | | | |
|----|----------------------------------------------------------------|---|-----|--|--|
| 19 | Battery along with Installation and wiring Shifting of UPS and | 1 | No. | | |
| | Total | | | | |

Estimate for Data Cabling Work

UCO BANK, KATRA BRANCH

| Sr. No: | Description of Items | Quantity | Unit | Rate | Amount |
|---------|---------------------------------------------------------------------------|----------|------|------|--------|
| 1. | SITC of CAT-6 Cable of D-link make in existing conduit complete | 60R | Mtr | | |
| 2. | SITC of Cat-6 information outlet (I.O.) face plate and Gang box of D-LINK | 5 | Each | | |
| 3. | SITC of mounting Cords 1 Mtr. Cat-6 D-LINK | 5 | Each | | |
| 4. | SITC of mounting cords 2 Mtr. Cat-6 D-Link | 5 | Each | | |
| 5. | SITC of 24 port jack panel Cat-6 D-Link | 0. | Each | | |
| 6. | Supply and installation of 19"u" Rack | 0 | Each | | |
| 7. | P/F of PVC Conduit 25mm | 69R | Mtr | | |
| | Total | | | | |

| Sr. No. | Estimate Type | Amount (Rs) |
|---------|-------------------------|-------------|
| 1 | Furniture & Fixing Work | |
| 2 | Electrical Work | |
| 3 | Data Cabling Work | |
| | Total | |