

B.O.Q INTERIOR WORK FOR UCO BANK , ATM AT-KEONJHAR .

Sl. No.	Particulars	Units	Qty.	Rate. (Rs)	Amount. (Rs)
1	PANELLING				
	Providing , fitting & fixing paneling work made out of 1"X1.5" almunium section frame work. The sections are to be placed 600mm c/c. 6 mm ply to be nailed over the suface of the frame work and 1mm thick laminate of approved shade be pasted over the ply surface as per design. The edges to be covered with decorative beading, including two coat of wax polish to superior finish, including cost of all labour & material .	Sft	190.00		
2	FRONT ENTRANCE DOOR AND				
	Providing and fixing Entrance Door (glazed) as per drawing in black Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & sides glazed with 12 mm thick glass of approved make with chemical eaching design as per drg. . Item to include all necessary hardware of Stainless Steel finish as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion (it include SS finished H type 1'-6" long door handle)	Sft	24.50		
	b) Fixed portion	Sft	40.00		
3	FLOOR SPRING				
	Providing and fixing Godrej make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	1.00		



4	FALSE CEILING				
	Providing & fixing at site plain Gypsum Board false ceiling made out of 12.5 mm thick paper reinforced gypsum board sheets to be fixed with main frame channels of size(80 mm x 26 mm x 0.5 mm) at every 450 mm c/c, intermediate channels of size(15 mm x 45 mm x 0.9 mm) at every 1220 mm c/c with perimeter channel 20 mm x 26 mm x 0.5 mm all along the wall shall be provided . The frame work to be suspended with strap bolts as recommended using rail plugs 12.5 mm dia x 35 mm long with 6 mm dia bolt and soffit cleat. Ceiling surface is to paint with two coats of distemper to get a smooth & even look including the cost of hard ware fittings,all labour & materials.	Sft	55.00		
5	Façade of front entrance door.				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.It also contain the shutter and lock system for the collapsable gate to hide at the entrance as per instruction of the architect. The work should be completed in all respect including all labour and material.	Sft	65.00		
TOTAL				Rs.	
Interior work of Branch			Rs.		
Interior work of ATM			Rs.		
TOTAL			Rs.		

